

Section	Item	Description	Unit	Quantity	Rate (HK\$)
Substructure	A1	Excavation for foundation (machine dig)	m3	350.00	340.00
Substructure	A2	Blinding concrete grade 20	m3	40.00	1,600.00
Substructure	A3	Concrete grade 35 in foundations	m3	120.00	1,750.00
Substructure	A4	Reinforcement bar supply and fix (T16)	kg	15,000.00	11.50
Substructure	A5	Formwork to foundation faces	m2	800.00	460.00
Superstructure	B1	Masonry wall in cement sand mortar	m2	650.00	660.00
Superstructure	B2	Reinforced concrete column grade 35	m3	85.00	1,850.00
Superstructure	B3	Formwork to columns	m2	900.00	470.00
Superstructure	B4	Reinforcement bar supply and fix (T20)	kg	22,000.00	12.00
Superstructure	B5	Precast concrete slab panel	m2	1,400.00	1,450.00
Finishes	C1	Cement sand plastering to wall	m2	1,300.00	175.00
Finishes	C2	Emulsion painting to wall	m2	2,400.00	52.00
Finishes	C3	Ceramic wall tiling	m2	900.00	2,850.00
Finishes	C4	Waterproofing membrane to roof	m2	700.00	265.00
Finishes	C5	Ceiling false ceiling with metal frame	m2	1,100.00	380.00
External Works	D1	Demolition of existing structures	m3	90.00	480.00
External Works	D2	Excavation and disposal of spoil	m3	420.00	355.00
External Works	D3	uPVC drainage pipe 110mm	m	320.00	285.00

Section	Item	Description	Unit	Quantity	Rate (HK\$)
External Works	D4	Road base and asphalt surfacing	m2	1,500.00	620.00
External Works	D5	Scaffolding to external walls	m2	1,200.00	115.00
Services	E1	Electrical installation point	no.	180.00	950.00
Services	E2	Plumbing installation point	no.	120.00	1,050.00
Services	E3	Fire alarm detection point	no.	95.00	1,250.00
Services	E4	LV switchboard supply and install	no.	2.00	185,000.00
Joinery	F1	Hollow core door with frame and ironmongery	no.	45.00	2,750.00
Joinery	F2	Aluminium window with glazing	m2	220.00	3,100.00
Joinery	F3	Scaffolding to external walls	m2	1,200.00	118.00