

BILL OF QUANTITIES

Repairs and Renovation Works for a Community Hall
Contract No. CH/2026/014 | Client: District Council | August 2026
This document is a test sample generated for the Smart QS Copilot screening app. Rates are illustrative and must not be used for tendering.

A. PRELIMINARIES

Item	Description	Unit	Qty	Rate (HK\$)
A1	Site establishment, safety and temporary works	LS	1	150,000
A2	Building services testing and commissioning	LS	1	95,000

B. DEMOLITION

Item	Description	Unit	Qty	Rate (HK\$)
B1	Demolition of existing partition walls	m2	180	480
B2	Removal of existing floor finishes	m2	350	95
B3	Disposal of debris off site	m3	45	320
B4	Demolition of existing partition walls	m2	60	485

C. FINISHES

Item	Description	Unit	Qty	Rate (HK\$)
C1	Cement sand plastering to walls (patch work)	m2	600	175
C2	Emulsion painting to walls and ceilings	m2	300	550
C3	Ceramic wall tiling to toilets	m2	220	310
C4	Waterproofing membrane to wet areas	m2	140	530
C5	Ceramic floor tiling to entrance lobby	m2	150	330
C6	Suspended ceiling with metal frame	m2	480	375
C7	Floor screeding to receive finishes	m2	500	135

D. DOORS AND WINDOWS

Item	Description	Unit	Qty	Rate (HK\$)
D1	Hollow core door with frame and ironmongery	no.	12	2,750
D2	Aluminium window with glazing	m2	35	3,150

E. SERVICES

Item	Description	Unit	Qty	Rate (HK\$)
E1	Electrical installation point	no.	160	950
E2	Plumbing installation point	no.	40	1,080
E3	Fire alarm detection point	no.	30	1,250
E4	LV switchboard supply and install	no.	1	185,000
E5	AC outlet point	no.	25	1,350

Item	Description	Unit	Qty	Rate (HK\$)
E6	Sanitary fitting supply and install	no.	10	980

F. EXTERNAL AND MISCELLANEOUS

Item	Description	Unit	Qty	Rate (HK\$)
F1	Scaffolding to external walls	m2	400	118
F2	Stainless steel handrail supply and fix	m	45	850
F3	Builder's work for services openings	no.	30	450